FED. ROAD DIV. No.	STATE	F A PROJECT NO.	FISCAL YEAR	SHEET No.
3	FLA.			1

BOOK NUMBERS 1014055, 1014073, 1014074

BEGIN SURVEY
STA. 330+00.00 (Canal St.)
STA. 28+00.91 (Americus Ave.)

BEGIN SURVEY
STA. 230+00.00 (Atlantic St.)=
STA. 35+42.00 (Americus Ave.)

BEGIN SURVEY
STA. 130+00.00 (Selma St.)=
STA. 39+27.24 (Americus Ave.)

Curve Data On Exist. Americus Ave.

PI.	Sta. 40+59.16
Δ	5°13'40" Lt.
D	1°30'00"
T	523.14'
L	1043.56'
R	1145.92.16
P.C.	Sta. 25+36.02
P.T.	Sta. 45+81.58

BEGIN SURVEY
STA. 30+00.00 (Santa Anna St.)=
STA. 46+97.27 (Americus St.)

SEC. 5, T-7-S, R-11-W
Scale: 1"=100'

PORT ST. JOE BEACH UNIT ONE
PLAT BOOK 1, PAGE 58

REFERENCE POINTS
NO SCALE

END SURVEY
STA. 341+94.84 (Canal St.)=
STA. 30+00.00 (Georgia Ave.)

END SURVEY
STA. 243+70.87 (Atlantic St.)=
STA. 37+87.63 (Georgia Ave.)

UTILITY OWNERS
TELEPHONE: St. Joseph Tele. Teleg. Co.
POWER: Florida Power Co.

END SURVEY
STA. 143+69.97 (Selma St.)=
STA. 42+22.72 (Georgia Ave.)

END SURVEY
STA. 43+70.00 (Santa Anna St.)=
STA. 50+66.58 (Georgia Ave.)

B.I. Number 323762

STATE OF FLORIDA
DEPARTMENT OF TRANSPORTATION

RIGHT OF WAY MAP

STATE ROAD No. GULF COUNTY

	BY	DATE
DRAWN		
TRACED	I.L.C.	11-15-76
CHECKED	P.E.C.	12-13-76
COMPARED		
INDEXED		

APPROVED BY — DATE
DISTRICT ENGINEER — 12-1-76
ENGINEER OF RIGHT OF WAY — 1-4-77
STATE HIGHWAY ENGINEER

REVISION	BY	DATE
Stations	BW	5-12-77

SECTION 51550-2607 SHEET 1 OF 1

STREETS IN PORT ST. JOE BEACH